WAC 222-24-030 Road construction. (1) Right of way timber shall be removed or decked in suitable locations where the decks will not be covered by fill material or act as support for the fill or embankment.

*(2) In permanent road construction, do not bury:

(a) Loose stumps, logs or chunks if they will contribute more than 5 cubic feet in the load-bearing portion of the road.

(b) Any significant amount of organic debris within the top 2 feet of the load-bearing portion of the road.

(c) Excessive accumulation of debris or slash in any part of the load-bearing portion of the road fill.

(3) **Compact fills.** During road construction, fills or embankments shall be built up by layering. Each layer shall be compacted by operating the tractor or other construction equipment over the entire surface of the layer. Chemical compacting agents may be used in accordance with WAC 222-38-020.

*(4) **Stabilize soils.** Erodible soil disturbed during road construction and located where it could reasonably be expected to enter the stream network must be seeded with noninvasive plant species. The use of local area native species, adapted for rapid revegetation is preferred. Treatment with other erosion control measures may be approved by the department.

*(5) **Channel clearance.** Within 50 feet upstream from a culvert inlet clear stream channel of all debris and slash generated by the operations that reasonably may be expected to plug the culvert prior to the removal of equipment from the vicinity, or the winter season, whichever is first. (See the board manual, section 4 for debris removal guidelines.)

*(6) **Drainage**.

(a) All required ditches and drainage structures shall be installed concurrently with the construction of the roadway.

(b) Uncompleted road construction to be left over the winter season or other extended periods of time shall be drained by outsloping or drainage structures. Water bars and/or dispersion ditches may also be used to minimize eroding of the construction area and stream siltation. Water movement within wetlands must be maintained.

*(7) **Moisture conditions.** Construction shall be accomplished when moisture and soil conditions are not likely to result in excessive erosion and/or soil movement, so as to avoid damage to public resources.

*(8) End haul/sidecasts. End haul or overhaul construction is required where significant amounts of sidecast material would rest below the 100-year flood level of any typed water, within the boundary of a Type A or Type B Wetland or wetland management zones or where the department determines there is a potential for mass soil failure from overloading on unstable slopes or from erosion of side cast material causing damage to the public resources.

*(9) **Waste disposal.** When spoil, waste and/or other debris is generated during construction, this material shall be deposited or wasted in suitable areas or locations and be governed by the follow-ing:

(a) Spoil or other debris shall be deposited above the 100-year flood level of any typed waters or in other suitable locations to prevent damage to public resources. The material shall be stabilized using the recommended schedule and procedures found in the board manual, section 3.

(b) All spoils shall be located outside of Type A and Type B Wetlands and their wetland management zones. Spoils shall not be located within the boundaries of forested wetlands without written approval of the department and unless a less environmentally damaging location is unavailable. No spoil area greater than 0.5 acre in size shall be allowed within wetlands. (See WAC 222-24-015, Construction in wetlands.)

(10) **Disturbance avoidance for northern spotted owls.** Road construction, operation of heavy equipment and blasting within a SOSEA boundary shall not be allowed within 0.25 mile of a northern spotted owl site center between March 1 and August 31, provided that, this restriction shall not apply if:

(a) The landowner demonstrates that the owls are not actively nesting during the current nesting season; or

(b) The forest practice is operating in compliance with a plan or agreement developed for the protection of the northern spotted owl under WAC 222-16-080 (6)(a), (e), or (f).

(11) Disturbance avoidance for marbled murrelets.

(a) Road construction and operation of heavy equipment shall not be allowed within 0.25 mile of an occupied marbled murrelet site during the daily peak activity periods within the critical nesting season; and

(b) Blasting shall not be allowed within 0.25 mile of an occupied marbled murrelet site during the critical nesting season.

(c) Provided that, these restrictions shall not apply if the forest practice is operating in compliance with a plan or agreement developed for the protection of the marbled murrelet under WAC 222-16-080 (6)(a) or (c).

[Statutory Authority: Chapter 34.05 RCW, RCW 76.09.040, [76.09.]050, [76.09.]370, 76.13.120(9). WSR 01-12-042, § 222-24-030, filed 5/30/01, effective 7/1/01. Statutory Authority: RCW 76.09.040 and chapter 34.05 RCW. WSR 97-24-091, § 222-24-030, filed 12/3/97, effective 1/3/98; WSR 97-15-105, § 222-24-030, filed 7/21/97, effective 8/21/97. Statutory Authority: Chapters 76.09 and 34.05 RCW. WSR 96-12-038, § 222-24-030, filed 5/31/96, effective 7/1/96. Statutory Authority: RCW 76.09.060, 76.09.040 and chapter 34.05 RCW. WSR 92-23-056, § 222-24-030, filed 11/17/92, effective 12/18/92. Statutory Authority: RCW 76.09.040, 76.09.050 and chapter 34.05 RCW. WSR 92-15-011, § 222-24-030, filed 7/2/92, effective 8/2/92. Statutory Authority: RCW 76.09.040. WSR 87-23-036 (Order 535), § 222-24-030, filed 11/16/87, effective 1/1/88. Statutory Authority: RCW 76.09.040 and 76.09.050. WSR 82-16-077 (Resolution No. 82-1), § 222-24-030, filed 8/3/82, effective 10/1/82; Order 263, § 222-24-030, filed 6/16/76.]