

**WAC 296-96-24252 Testing of safeties.** Safeties shall be tested before inclined private residence conveyances for transporting property are put into service. Safeties shall be tested while the conveyance is carrying its rated load.

[Statutory Authority: Chapter 70.87 RCW. WSR 18-18-070, § 296-96-24252, filed 8/31/18, effective 10/1/18.]