

WAC 296-870-60030 Cable stabilization. (1) You must make sure hanging lifelines and all other cables not in tension are stabilized after the initial two hundred feet (61 m) of vertical travel of the working platform and every two hundred feet (61 m) thereafter.

(2) You must make sure hanging cables which are in constant tension, other than suspended wire ropes, are stabilized after an initial six hundred feet (183 m) of vertical travel of the working platform and at intervals of six hundred feet (183 m) or less thereafter.

[Statutory Authority: RCW 49.17.010, 49.17.040, 49.17.050. WSR 15-23-086, § 296-870-60030, filed 11/17/15, effective 12/18/15. Statutory Authority: RCW 49.17.010, 49.17.040, 49.17.050, 47.17.060. WSR 06-19-075, § 296-870-60030, filed 9/19/06, effective 1/1/07.]