

WAC 296-803-50030 Verify that the machine or equipment is safe before starting work. You must make sure the authorized employee verifies that the machine or equipment that has been locked out or tagged out has been isolated from all energy sources and deenergized before starting work.

[Statutory Authority: RCW 49.17.010, 49.17.040, 49.17.050, and 49.17.060. WSR 17-18-075, § 296-803-50030, filed 9/5/17, effective 10/6/17; WSR 04-15-105, § 296-803-50030, filed 7/20/04, effective 11/1/04.]